

15-165-20419-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rush County, Sec. 33 Twp. 17S Rge. ~~XXX~~ 20 (W)

Location as "NE/CNW/SW" or footage from lines C SW SE
Lease Owner Pickrell Drilling Company
Lease Name Georg "C" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 5 1972
Application for plugging filed January 5 1972
Application for plugging approved January 5 1972
Plugging commenced January 5 1972
Plugging completed January 5 1972
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4193' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	263'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug @ 550' w/70 Sacks, Middle Plug @ 240' w/20 Sacks,
Top Plug @ 40' w/10 Sacks.


RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1972
CONSERVATION DIVISION
Wichita, Kansas
01-12-1972

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Kansas
(Address)

Subscribed and sworn to before me this 10th day of January, 1972
Esther Lamone
My commission expires January 19, 1973
Esther Lamone Notary Public.



ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 12/28/71

Rotary Drilling Completed 1/5/72

LOCATION: Georg "C" No. 1, C SW SE Section 33-17S-20W
Rush County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Run 7 Jts. 8-5/8" surface casing set @ 263'. Cemented with
140 Sacks. Completed 8:45 P.M. Circulated.

No oil string run. D & A, Plugged 3 P.M. January 5, 1972.

LOG

(Figures indicate bottom of formation -- measurements from top of rotary bushing.)

130	Clay, Post Rock	C.F.S.
265	Shale & Sand Streak	4080
320	Shale	4090
415	Sand	4095
670	Shale	4115
815	Red Beds	4140
1060	Sand	4193
1399	Shale - Redbeds	
1440	Anhydrite	
1875	Shale	
2160	Shale & Lime	
2380	Lime - Shale	
3130	Lime	
3410	Shale - Lime	Slope Tests
3540	Sandy Lime & Shale	2000
3650	Shale & Lime	2500
3750	Lime	3000
3850	Lime & Shale	3500
4140	Lime	4000
4193	Chert & Lime, Miss., RTD	

RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1972
CONSERVATION DIVISION
Wichita, Kansas
01-12-1972

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 10th day of January, 1972, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: January 19, 1973

Esther Lamone
Notary Public Esther Lamone