

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Rush County, Sec. 11 Twp. 17S Rge. (E) 20 (W)  
Location as "NE/CNW&SW&" or footage from lines C SW SW  
Lease Owner Pickrell Drilling Company  
Lease Name House "A" Well No. 1  
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 29, 1966  
Application for plugging filed July 29, 1966  
Application for plugging approved July 29, 1966  
Plugging commenced July 29, 1966  
Plugging completed July 29, 1966  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Leo F. Massey, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3970 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	250'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 420'. Set plug. Cemented with

25 sacks cement. Heavy mud to 240'. Set plug.

cemented with 20 sacks cement. Heavy mud to

40'. Set plug. Cemented with 10 sacks cement

to bottom of cellar. Plugged rat hole with 2

sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 5 1966  
08-05-1966  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
C. W. SEBITS (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

C. W. Sebits  
705 Fourth National Bank Bldg., Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of August, 1966

L. M. Whiting  
L. M. Whiting,

Notary Public.

My commission expires

May 10, 1970

15-165-30128-00-00  
**ROTARY DRILLING LOG**

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Bldg.  
Wichita, Kansas 67202  
Rotary Drilling Commenced 7-20-66  
Rotary Drilling Completed 7-29-66

LOCATION: House No. 1, G SW SW Section 11-17S-20W,  
Rush County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: (12 Jts.) 8 5/8" surface casing set at 250' with 165 sacks cement.  
Circulated. Completed 6:30 PM July 20, 1966. No oil string run.  
D. & A.

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

35	Clay	<u>C. F. S.</u>
600	Shale & Shells	3910
770	Red Beds	3922
1025	Sand	3940
1335	Red Beds, Shale & Shells	3950
1368	Anhydrite	3960
1620	Shale & Shells	3970
2040	Shale	
2365	Lime & Shale	
2565	Lime	<u>Slope Tests</u>
2640	Lime & Shale	2000
2850	Shale	2500
3605	Lime & Shale	3000
3853	Lime	3500
3890	Pawnee	
3907	Lime, Shale & chert	
3940	Lime, Shale & Sand	<u>S. L. M.</u>
3950	Lime & Sand	Board 3876.35
3970	Arbuckle - T.D.	Strap 3874.73
		Difference 1.62 short

**RECEIVED**  
STATE CORPORATION COMMISSION

AUG 5 1966  
08-05-1966  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 3rd day of August, 19 66, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

L. M. Whiting  
L. M. Whiting, Notary Public