

15-165-02122-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rush County, Sec. 22 Twp. 18 Rge. 16 (E) (W)

Location as "NE/CNW/SW" or footage from lines \_\_\_\_\_  
Lease Owner Morgenstern & Specter  
Lease Name Schneider Well No. 2  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 7-12-56 19\_\_\_\_  
Application for plugging filed August 21, 1961 19\_\_\_\_  
Application for plugging approved August 22, 1961 19\_\_\_\_  
Plugging commenced 8/25/61 19\_\_\_\_  
Plugging completed 8/27/61 19\_\_\_\_  
Reason for abandonment of well or producing formation failure to produce profitably

NORTH


Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Hays, Kansas  
Producing formation Reagan Sand Depth to top 3538 Bottom 3589 Total Depth of Well 3590 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	1011.87'	none
				5 1/2" OD	3590 ft.	3045 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with sand to 3150 feet, Dumped 4 sacks - cement.  
Mudded hole up to 350 feet, Set a rock bridge.  
Dumped 20 sacks cement, Mudded hole up to 150 feet.  
Set a rock bridge, Dumped 20 sacks cement, Mudded hole - up to 40 feet.  
Set a rock bridge, Dumped ten sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
9-14-61  
SEP 14 1961

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor LYNCH CASING PULLING COMPANY NO. 457  
Address Rt. 4 GREAT BEND, KANSAS

STATE OF Kansas, COUNTY OF Russell, ss.  
Morgenstern & Specter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ruth E. Miller  
Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 29<sup>th</sup> day of August, 1961

My commission expires January 5, 1965.

Ruth E. Miller  
Notary Public.




K-165-02122-0000  
 WELL LOG BURBU-KANSAS GEOLOGICAL SOCIETY  
 500 East Merriell, Wichita, Kansas

Company- WELCH & OLSSON DRILG. CO., INC.  
 Farm- Schnoider No. 2

SEC. 23 T. 18 R. 16W  
 NW 5<sup>th</sup> SW

Total Depth. 3590'  
 Comm. 7-2-56 Comp. 7-12-56  
 Shot or Treater.  
 Contractor. Welch & Olsson Drilg. Co., Inc.  
 Issued. 8-25-56

County Dist. KANSAS



CASING:  
 8 5/8" 1011.87' w/450 sx cem.  
 5 1/2" 3589' w/75 sx cem.

Elevation. 1969' RB

Prod. date 25 Bbls.

Figures indicate Bottom of Formations

shale-shells	50
shale-red bed	335
shale-pyrite sand	430
sand	610
sand-shale	690
shale-shells w/sand stks	900
shale-shells	990
Anhydrite	1020
sdv anhydrite	1040
shale-red bed	1200
shale-shells	1730
shale-shells w/lime stks	1820
shale w/lime stks	2050
lime-shale	2235
shale-lime	2360
shale w/lime stks	2630
shale-shells	2785
shale-lime	3035
lime-shale	3335
lime	3539
sand	3590
Total Depth	

TOPS:	
Heebner	2185
Toronto	3203
Douglas	3218
Lansing-Kansas City	3240
B/Kansas City	3471
Conglomerate	3507
Reagan sand	3538
Pre-Cambrian	3567
Granite	3588