

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rush County. Sec. 24 Twp. 18S Rge. 16W (E) (W)

Location as "NE/CNW/SW" or footage from lines. Center NW/4

Lease Owner Herndon Drilling Company

Lease Name Phillip J. Brack Well No. 1

Office Address Drawer 489, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed 11/9/36 19

Application for plugging filed 7/26/56 19

Application for plugging approved 7/28/56 19

Plugging commenced 9/22/56 19

Plugging completed 9/26/56 19

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. R. M. Brundage, Box 283, Hoisington, Ks.

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3480 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				15 1/2"	200'	None
				10"	498'	None
				7"	3456'	1755'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled the hole with sand from 3480' to 3440' and ran 6 sacks of cement which filled to 3405'. Circulated the hole with 15 sacks of jell mud. Mudded the hole to 310'. Set a 10" rock bridge and ran 25 sacks of cement which filled to 250'. Mudded the hole to 30', set a 10" rock bridge and ran 10 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company, Inc.

Address Chase, Kansas

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

Jack Herndon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Drawer 489, Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of October 19 56

My commission expires 1/27/60

Notary Public.

PLUGGING
FILE SEC. 24 T. 18 R. 16W
BOOK PAGE 84 LINE 25

RECEIVED
STATE CORPORATION COMMISSION
10-9-56
OCT 9 1956
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg, Wichita, Kansas.


HERNDON DRILLING CO.
P.J. Brack No. 1.

15-165-02150-0000

SEC. 24 T. 18 R. 16W.
Cen NW $\frac{1}{4}$

Total Depth. 3480
Comm 10-17-36 Comp. 11-9-36
Shot or Treated.
Contractor.
Issued. 2-6-37

County Rush.



CASING.

15" 200'
10" 938'
7" 3458'

Elevation.

Production 38,000,000G.

Figures Indicate Bottom of Formations.

soil	30	lime and shale	3440
sand	150	shale red	3450
shale	200	shale red	3455
shale and sand	285	sand hard	3458
iron	290	shale green	3466
sticky shale	387	sand	3480
sand and shale red	500	Total Depth.	
shale	525		
sand	590		
red rock	740		
sand	765		
shale and red rock	925		
shale	937		
anhydrite	948		
anhydrite	970		
shale and red rock	1035		
shale and shells	1660		
broken lime	1710		
shale and shells	1765		
lime	1800		
broken lime	2015		
lime	2105		
broken lime	2130		
lime	2225		
broken lime	2320		
lime	2340		
shale	2370		
lime	2400		
lime	2430		
lime and shale bks	2470		
lime and shale	2525		
lime	2540		
lime broken	2590		
shale and shells	2650		
broken lime	2680		
shale	2700		
lime	2810		
shale	2830		
lime	2855		
lime	3100		
shale	3110		
lime	3120		
lime	3435		

RECORDED
STATE COMMISSION

JUL 7-28-56

CONSULTING ENGINEER

PLUGGING
FILE SEC 24 T. 18 R. 16W
BOOK PAGE 84 LINE 25