

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR AFG Energy, Inc.

ADDRESS P.O. Box 605

PHONE#(913) 625-6374 OPERATORS LICENSE NO. 3456

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-20-92 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Cherokee Sand Depth to Top 3836' Bottom 3839' T.D. 3839'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Cherokee Sand	Oil & water	3836	3839	8 5/8"	603	None
				4 1/2"	3837.5	None
				DV - 1305' - 550'		sxs.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Hooked to 8 5/8" casing - Pressured to 300#. Hooked to 4 1/2" casing - mixed 300# hulls alone. Then 200# hulls in first 40 sxs. Mixed 145 sxs. total of 60/40 poz. mix. 8% gel. Pumped at 2000#. SIP - 1800#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. RECEIVED

Address Russell, KS 67665 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy, Inc. **OCT 22 1992**

STATE OF Kansas COUNTY OF Russell, ss. **10-22-1992**
 CONSERVATION DIVISION
 Wichita, Kansas

Terry W. Piesker (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) P.O. Box 605, Russell, KS

SUBSCRIBED AND SWORN TO before me this 21st day of October, 1992

Pamela K. Steckel
 Notary Public

My Commission Expires: 11-19-92

