

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR AFG Energy, Inc.

ADDRESS P.O. Box 605, Russell, KS 67665

PHONE # (913) 483-6213 OPERATORS LICENSE NO. 3456

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Penn Sand-LKC Depth to top 3837' bottom 3840' T.O. 3840'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORDS

Formation	Content	From	To	Size	Put in
<u>Penn Sand</u>	<u>Oil</u>	<u>3837</u>	<u>3840</u>	<u>8 5/8"</u>	<u>601</u>
<u>Lansing-KC</u>	<u>Oil</u>	<u>3503</u>	<u>09</u>	<u>4 1/2"</u>	<u>3838.5</u>

RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1991
08-16-1991
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Hooked to 4 1/2" pumped 4 sxs - 400# hulls mixed in 19 bbls. water. Mixed 160 sxs. 65/35 Poz mix 5% gel & 100# hulls in first part - pressured to 1000# & held on well & shut in. Hooked to 8 5/8" casing - mixed 15 sxs. & pressured to 500# and held.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Allied Cementing, Inc. License No. _____
Address Russell, KS 67665

STATE OF Kansas COUNTY OF Russell, ss.

Terry W. Piesker (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) P.O. Box 605, Russell, KS



SUBSCRIBED AND SWORN TO before me this 15th day of August, 1991

Pamela K. Steckel
Notary Public

My Commission expires: 11-19-92