

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE NAME Jacobs "B"

WELL NUMBER 2

SPOT LOCATION SE NW NW

SEC. 30 TWP. 17 SRGE. 18 (E) or (W)

COUNTY Rush

Date Well Completed 9-1-81

Plugging Commenced 8-28-91

Plugging Completed 8-28-91

LEASE OPERATOR AFG Energy, Inc.

ADDRESS P.O. Box 605, Russell, KS

PHONE # (913) 483-6213 OPERATORS LICENSE NO. 3456

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing formation Penn Sand Depth to top 3835 bottom 3837 T.D. 3856

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORDS

Formation	Content	From	To	Size	Put in	Failed out
<u>Penn Sand</u>	<u>Oil &amp; Water</u>	<u>3835</u>	<u>3837</u>	<u>8 5/8"</u>	<u>599</u>	<u>None</u>
				<u>5 1/2"</u>	<u>3853</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Hooked to 5 1/2" - Pumped 200#

hulls - followed w/300# hulls mixed in first part of cement. Mixed 300 sxs. 65/35 Poz, 5% gel. Max. Press. - 1000#, Shut in - 400#. Loaded 8 5/8" w/cement and held OK - got 1 sx. in.


(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing  
Address Russell, KS 67665

License No. \_\_\_\_\_  
STATE CORPORATION COMMISSION  
**RECEIVED**  
08-29-1991  
**AUG 29 1991**

STATE OF Kansas COUNTY OF Russell, ss.

Terry W. Piesker (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Terry W. Piesker  
(Address) P.O. Box 605, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 28<sup>th</sup> day of August, 1991

Pamela K. Steckel  
Notary Public

My Commission expires: 11-19-92