

15-165-20387-00-00

Form CP-3
Rev. 6-4-68

KANSAS

4
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 3 1971

CONSERVATION DIVISION
Wichita, Kansas

05-03-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company
Complete Address 705 Fourth National Bank Bldg., Wichita, Kansas
Lease Name Sloan "A" Well No. 1
Location SE SE SW Sec. 30 Twp. 17 Rge. (E) (W) 20
County Rush Total Depth 4218'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Go. Tools
Address License No.

Operation Completed: Hour 7 A Day 26 Month 4 Year 1971

The above well was plugged as follows:

RTD 4218' 8 5/8 csg set at 413' cwc
Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 50 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 5/3/71
INV. NO. 3634-11

Signed: Lew L. Massey
Well Plugging Supervisor