

15-165-20429-00-00

Form CP-3
Rev. 6-4-68

KANSAS

al
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 14 1972
04-14-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company
Complete Address 705 Fourth National Bank Bldg., Wichita, Kansas
Lease Name Smith "R" Well No. 1
Location NE SW SE Sec. 31 Twp. 17 Rge. (E) (W) 20
County Rush Total Depth 4200'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 7 A Day 12 Month 4 Year 1972

The above well was plugged as follows:

RTD 4200' 8 5/8 csg set at 257' cwc. Cmt. Mat. 50-50 poz cmt W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 50 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/17/72
INV. NO. 5553-W

Signed: Red F. Messerly
Well Plugging Supervisor