

15-165-20116-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 31 1972

CONSERVATION DIVISION  
Wichita, Kansas

07-31-1972

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name National COoperative Refinery Association

Complete Address P. O. Box 6 Great Bend, Kansas 67530

Lease Name Moran Unit # 1 Well No. 1

Location C NW SW Sec. 7 Twp. 17 Rge. (E) (W) 20

County Rush Total Depth 4132'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor       

Address        License No.       

Operation Completed: Hour 12 N Day 25 Month 7 Year 1972

The above well was plugged as follows:

Total Depth 4132' 8 5/8 csg set at 397' cwc 275 sk.

5 1/2 csg set at 4131' cw 125 sk cmt. DV tool set at 1455' cwc 450 sk.

5 1/2 csg FBTD 4093' with perf. (4045-4048)

No pipe recovered.

Filled 5 1/2 csg W/sd (4000' - 4093') dumped 5 sk cmt (3965-4000')

Mud to 550' -set rock & sand bridge (500'-550')

Dumped 3 yds readymix cmt from 500' to base of cellar.

Checked annulus -full of cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 8/1/72

INV. NO. 6096-W