

15-165-20310-00-00

**KANSAS**

Form CP-3  
Rev. 6-4-68

**STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT**

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
06-10-1975  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Chief Drilling Company

Complete Address 905 Century Plaza, Wichita, Kansas 67202

Lease Name Campbell "A" Well No. 1

Location SE NE SE Sec. 6 Twp. 17 Rge. (E) (W) 20

County Rush Total Depth 4018'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Kelso Pipe Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11 A Day 7 Month 6 Year 1975

The above well was plugged as follows:

Total Depth 4018' 8 5/8 csg set 477' cwc 300 sk.

5 1/2 csg set 4014' cw 150 sk cem.

5 1/2 csg PBD 4013' with top perf. (3950')

Filled 5 1/2 csg W/sd (4013-3925) dumped 4 sk cem W/dump bailer. (3925-3895)

Cutoff & recovered 3225' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg with 25 sk gel & water W/300 lbs hulls -released

plug & 130 sk 50-50 poz 6% by Allied Cem. Co. Max. PP 500 lbs. SIP 200 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

**INVOICED**

DATE 6/13/75

INV. NO. 1464-W