

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -165 -20,626 -00-00 (of this well)

04-04-1977  
04-04-1977

Operator's Full Name F & M Oil Co., Inc.

Complete Address 505 Union Center, Wichita, Kansas

Lease Name Berthold Well No. 1

Location E/2 E/2 NE/4 Sec. 12 Twp. 17 Rge. (E) (W) 20

County Rush Total Depth 3900'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Duke Drlg.

Address Great Bend, Kansas License No.       

Operation Completed: Hour 7:15 P Day 30 Month 3 Year 1977

The above well was plugged as follows:

RTD 3900' 8 5/8 csg set 255' cwc 200 sx. Flg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 420' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: [Signature]  
Well Plugging Supervisor

DATE 4-5-77

INV. NO. 4904-W