

15-165-20168-00-00

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202RECEIVED  
STATE CORPORATION COMMISSION  
AUG 5 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
08-05-1968Operator's Full Name Rains & Williamson Oil Company, Incorporated,Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.Lease Name Temple Well No. 1Location CNW-NW-NE Sec. 12 Twp. 17 Rge. (E) (W) 20County Rush Total Depth 3871Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Above

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 4:30 PM Day 31 Month 7 Year 1968

The Above well was plugged as follows:

257'--8 5/8" Surface casing, cement circulated with 155 Sx.Circulated hole with heavy mud. Pulled DP to 600' and displaced 100 Sx. cement thruDP from 600' to 280'. Pulled DP to 270' and displaced 20 Sx. cement thru DP from 270'to 210'. Pulled DP, set bridge @ 40' with  $\frac{1}{2}$  sack hulls and 10 Sx. cement to bottomof cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Fitch

Well Plugging Supervisor

DATE 8/5/68INV. NO. 8225-U