

15-165-20115-00-00

Form CP-3
Rev. 6-26-62

P KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
FEB 13 1968
CONSERVATION DIVISION
Wichita, Kansas
02-13-1968

Operator's Full Name Neven H. Veail

Complete Address: 1401 McKinley Great Bend, Kansas

Lease Name Bott Well No. 1

Location C NE SW Sec. 35 Twp. 17 Rge. 20 (E) (W) X

County Rush Total Depth 4070'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Peel Bros. Inc.,

Address: Hosington, Kansas License No. _____

Operation Completed: Hour 7[~]A Day 10 Month 2 Year 1968

The Above well was plugged as follows:

RTD 4070' 8 5/8 csg set at 274' cwc 160 sc. Cem. Mat. 100 sc cem. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 70 sc cem.

thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 2/13/68
INV. NO. 7260-W