

15-165-20537-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

JUN 2 1975

06-02-1975

Operator's Full Name B&B Drlg., Bill J. Porter & Slop Exploration Co.
Complete Address 720 Union Center, Wichita, Kansas
Lease Name Geopge Well No. 1
Location C SE SW Sec. 34 Twp. 17 Rge. (E) (W) 20
County Rush Total Depth 4155'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor B&B Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 12:45 P Day 28 Month 5 Year 1975

The above well was plugged as follows:

RTD 4155' 8 5/8 csg set 261' cwr 160 sx. Flg. Mat. 50-50 poz. 2% total gel.
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.
Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sx cem plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Manner
Well Plugging Supervisor

INVOICED
DATE 6/2/75
INV. NO. 1422-w