

15-165-20474-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 17 1973
CONSERVATION DIVISION
Wichita, Kansas
10-17-1973

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Jet Drilling Company, Inc.

Complete Address 514 One Twenty Bldg., Wichita, Kansas

Lease Name Rixon Well No. 2

Location SW SE SE Sec. 21 Twp. 17 Rge. (E) (W)20

County Rush Total Depth 4047'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor C & G Drilling

Address Wichita, Kansas License No.

Operation Completed: Hour 9:30 A Day 16 Month 10 Year 1973

The above well was plugged as follows:

RTD 4047' 8 5/8 csg set at 470' cwc Cmt. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 50 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 dk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/17/73

INV. NO. 8027-11

Signed: Leo J. Masser
Well Plugging Supervisor