

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 04 1976
10-04-1976
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Irv Hardman

Complete Address 601 One Twenty Bldg., Wichita, Kansas 67203

Lease Name Rixom Well No. 1

Location C SW SE Sec. 21 Twp. 17 Rge. (E) (W) 20

County Rush Total Depth 4055'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by Halliburton Cementing Co.

Address License No.

Operation Completed: Hour 11:30 A Day 1 Month 10 Year 1976

The above well was plugged as follows:

Total Depth 4055' 8 5/8 csg set 442' cwc

5 1/2 csg set 4055' cw 125 sk cem.

5 1/2 csg PBD 4049' & perf. (4043'-4047')

5 1/2 csg squeezed at 700' with 300 sk cem. No pipe recovered.

Halliburton mixed & pumped 30 sk 60-40 poz cem -displaced with 100 lbs hulls mixed

with 35 sx gel & water -released plug & capped with 70 sk 60-40 poz cem & shutin.

FPP 1300 lbs

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 10-5-76

INV. NO. 3933-W