

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-21731-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 27-17S-19W  
1100 feet from S Section Line, 2310 feet from W Section Line  
Lease/Unit Name: MORAN Well Number: 1  
County: RUSH Total Vertical Depth: 4000 feet

Operator License No.: 31514  
Op Name: THOROUGHbred ASSOCIATES L.L.C.  
Address: 8100 E. 22ND ST. - BUILDING 600  
WICHITA, KS 67226

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 225 **\$130.00**  
Production: Size feet:  
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 10/15/2001 3:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: ED MCKENNA Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 3900' WITH 50 SX CMT. 2ND PLUG AT 1350' WITH 50 SX CMT. 3RD PLUG AT 600' WITH 80 SX CMT. 4TH PLUG AT 260' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 10/15/2001 6:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

1ST PLUG AT 3900' WITH 50 SX CMT. 2ND PLUG AT 1350' WITH 50 SX CMT. 3RD PLUG AT 600' WITH 80 SX CMT. 4TH PLUG AT 260' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED

Plugged through: DP

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
OCT 22 2001  
10-22-01  
KCC WICHITA

INVOICED  
DATE 10-22-01  
INV. NO. 2002060830

OCT 18 2001

Form 2/3

ND