

1050172

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-20,516-0000

NE NE NE, SEC. 23, T 17 S, R 19 W/E

TECHNICIAN'S PLUGGING REPORT

_____ feet from N/S section line

_____ feet from W/E section line

Operator License # 5123

Lease Name Schwindt 'B' Well # 1

Operator: Pickrell Drilling Company

County Rush

Name & Address 110 North Market, Suite 205

Well Total Depth 3917 127.31 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____

Address P. O. Box 31, Russell, KS 67665

Company to plug at: Hour: 2:30 pm Day: 8 Month: March Year: 19 84

Plugging proposal received from Danny Biggs

(company name) Pickrell Drilling (phone) 316-792-2802

were: _____

Squeezed 5 1/2" with 175 sx cement at 700' and circulated to surface

1st plug pumped down 5 1/2" in sequence 1 sx hulls, 25 sx cement, 20 sx gel, 150 sx cement

Maximum pressure 1500# and shut-in pressure 300#

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:10 pm Day: 8 Month: March Year: 19 84

ACTUAL PLUGGING REPORT Squeezed 5 1/2" with 175 sx cement at 700' and circulated to

surface. 1st plug pumped down 5 1/2" in sequence 1 sx hulls, 25 sx cement, 20 sx gel,

150 sx cement.

Maximum pressure 1500# and shut-in pressure 300#

Bob Tarbutton gave the orders and Richard Lacey saw the plugging

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN) ✓

MAR 12 1984

3-17-84

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 3-13-84

INV. NO. 0740