

To: 1 070410  
STATE-CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 13-165-21,385-0000  
NW SW SE, SEC. 23, T 17 S, R 19 W/E  
990 feet from S section line  
2310 feet from E section line  
Lease Name Wilson "F" Well # 1  
County Rush 127.79  
Well Total Depth 3932 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 281

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5131  
Operator: Thunderbird Drilling, Inc.  
Name & Address P.O. Box 780407  
Wichita, KS 67278

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Dreiling Oil, Inc. License Number 5145  
Address RR 1, Box 1000, Victoria, KS 67671

Company to plug at: Hour: 12:45 p.m. Day: 10 Month: 9 Year: 1987

Plugging proposal received from Everett Mickelson  
(company name) Dreiling Oil, Inc. (phone) 913-735-2204

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2159'  
Anhydrite 1336-68'

1st plug at 3900' with 50 sx cement, 2nd plug at 1370' with 50 sx cement,  
3rd plug at 600' with 40 sx cement, 4th plug at 320' with 50 sx cement,  
5th plug at 40-0' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5 p.m. Day: 10 Month: 9 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 3900' with 50 sx cement,  
2nd plug at 1368' with 50 sx cement,  
3rd plug at 600' with 40 sx cement,  
4th plug at 320' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10' sx cement.

RECEIVED  
DATE 9-15-87  
SEP 15 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(if additional description is necessary, use BACK of this form.)

**INVOICED** observe this plugging.

Signed Dan Goodrow  
(TECHNICIAN)

DATE 9-17-87  
INV. NO. 18150

NOTICE OF INTENTION TO DRILL

GRID MOST DESIGNED

(see rules on reverse side)

Starting Date 9 4 87  
 month day year

API Number 15-165-21,385-00002

OPERATOR: License # 5131  
 Name Thunderbird Drilling, Inc.  
 Address P.O. Box 780407  
 City/State/Zip Wichita, Kansas 67278  
 Contact Person Burke Krueger  
 Phone (316) 685-1441

NW SW SE Sec 23 Twp 17 S, Rg 19 X East  
990 Ft. from South Line of Section  
2310 Ft. from East Line of Section

CONTRACTOR: License # 5145  
 Name Dreiling Oil, Inc.  
 City-State Victoria, Ks.

(Note: Locate well on Section Plat on reverse side)  
 Nearest lease or unit boundary line 330 feet  
 County Rush  
 Lease Name WILSON "F" Well # 1  
 Ground surface elevation 2159 feet MSL  
 Domestic well within 330 feet: yes X no  
 Municipal well within one mile: yes X no  
 Depth to bottom of fresh water 100  
 Depth to bottom of usable water 450 - 500  
 Surface pipe by Alternate: 280 X  
 Surface pipe planned to be set  
 Conductor pipe required None  
 Projected Total Depth 4000 feet  
 Formation Arbuckle

Well Drilled For: Well Class: Type Equipment:  
 Oil  SWD  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

If OWWO: old well info as follows:  
 Operator  
 Well Name  
 Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.  
 Date 8/25/87 Signature of Operator or Agent [Signature] Title Land Mgr.

For KCC Use:  
 Conductor Pipe Required 200 feet; Minimum Surface Pipe Required 200 feet per Alt. X  
 This Authorization Expires 2-26-88 Approved By [Signature] 8-26-87

*Move 9.3.87* *Set 280 + 8 5/8*  
*3 pod 4 1/2*

Sec. Twp. S, Rg. East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ <u>Arbuckle</u>	feet depth with <u>30</u>	sxs of <u>60-40</u>	poz <u>6.961</u>
2nd plug @ <u>Base of Anhydrite</u>	feet depth with <u>50</u>	sxs of <u>60-40</u>	poz
3rd plug @ <u>600</u>	feet depth with <u>40</u>	sxs of <u>"</u>	"
4th plug @ <u>300</u>	feet depth with <u>40</u>	sxs of <u>"</u>	"
5th plug @ <u>10</u>	feet depth with <u>10</u>	sxs of <u>"</u>	"
(2) Rathole with <u>1.9</u>	sxs	(b) Mousehole with <u>1.0</u>	sxs

PUSHER <u>Everett Nickelson</u>	FORMATION <u>Arb.</u>	1st PLUG @ <u>3900</u> FT. W/ <u>50</u> SX
TD <u>2112</u>	SURFACE PIPE <u>8 5/8" @ 281'</u>	2nd PLUG @ <u>1368</u> FT. W/ <u>50</u> SX
ANEHYDRITE <u>1368'</u>	ELEVATION <u>2159'</u>	3rd PLUG @ <u>600</u> FT. W/ <u>40</u> SX
STARTING TIME & DATE <u>12:45 PM</u>	COMPLETION TIME & DATE <u>5:00 PM</u>	4th PLUG @ <u>320</u> FT. W/ <u>50</u> SX
		RAT HOLE CIRCULATED W/ <u>15</u> SX
		MOUSE HOLE CIRCULATED W/ <u>10</u> SX
		WATER WELL PLUGGED W/ <u>SX</u>
		CEMENT COMPANY <u>Allied Supply Co. (Arbuckle, Kan.)</u>
		TECHNICIAN <u>Don Bradford</u>
		<u>Did See</u>

RECEIVED  
 COMMISSION  
9-15-87  
 SEP 15 1987

WICHITA, KANSAS