

1 120935

7-6

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,656-~~0000~~
N/2 NE SE, SEC. 2, T. 18 S, R. 16 W/SX
2310 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3456

Lease Name Schneider "B" Well # 2

Operator: AFG Energy Inc.

County Rush

Name & Address P.O. Box 458

Well Total Depth 3600 117.00 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1064

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company License Number 5929

Address 310 W. Central; Wichita, KS 67202

Company to plug at: Hour: 11 a.m. Day: 6 Month: 7 Year: 1994

Plugging proposal received from Rich Wheeler

(company name) Duke Drilling Company (phone) 316-267-1331

vers: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1090'

1st plug at 1090' with 50 sx cement,

2nd plug at 400' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:15 p.m. Day: 6 Month: 7 Year: 1994

ACTUAL PLUGGING REPORT 1st plug at 1090' with 50 sx cement;

2nd plug at 400' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, please use BACK of this form.)

INVOICED

(customer) observe this plugging.

DATE 7-14-94

Signature: Steve Middleton (TECHNICIAN)

INV. NO. 40816

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2
Rev. 01-