

3-29

298  
R

To: 1 070932  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 19- 165-20,094 - 0000  
NW NE NE, SEC. 7, T 17 S, R 19 W/E

TECHNICIAN'S PLUGGING REPORT

4950 feet from S section line  
990 feet from E section line

Operator License # 5086

Lease Name Elmore "A" Well # 1

Operator: Pintail Petroleum, Inc.  
Name & Address: 412 E. Douglas  
Wichita, KS 67202

County Rush 125.64  
Well Total Depth 3866 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 222

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour 2:30 p.m. Day: 29 Month: 3 Year: 19 91

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 3861' w/150 sx cement. Open hole at 3861-66', Squeezed at 1341' w/450 sx cement to 0'  
1st plug sand back to 3810' and dump 5 sx cement on top of sand through bailer,  
2nd plug run tubing to 1450' and circulate to surface,  
3rd plug pull tubing and squeeze with 100 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:45 p.m. Day: 29 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3810' and dumped 5 sx cement on top of sand through bailer,

2nd plug ran tubing in to 1450' and circulated with 115 sx cement,

3rd plug pulled tubing and pumped 10 sx cement.

Maximum pressure 1000 psi and shut in 0 psi.

Remarks: Used 60/40 Pozmix 8% gel by Allied. No casing recovery.  
(if additional description is necessary, use BACK of this form.)

(if necessary) observe this plugging.

RECEIVED  
STATE CORPORATION COMMISSION  
4-3-91  
APR 03 1991

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

Signed Dan Jordan (TECHNICIAN)

DATE 4-9-91

INV. NO. 31428