

To: **1.070019**  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5815  
Operator: C & R Drilling Company  
Name:   
Address P.O. Box 98  
Littleton, CO 80160

9-2  
API NUMBER 15- 165-21,710-0000  
165' N & 165' E of  
C NE NW, SEC. 4, T 17 S, R 19 WAX  
4785 feet from S section line  
3135 feet from E section line

Lease Name Younker Well # 1  
County Rush 126.10  
Well Total Depth 3880 feet  
Conductor Pipe: Size  feet  
Surface Casing: Size 8 5/8 feet 245

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A X

Other well as hereinafter indicated

Plugging Contractor Vonfeldt Drilling, Inc. License Number 9431  
Address P.O. Box 611, Russell, KS 67665-0611

Company to plug at: Hour:  Day: 1 Month: 9 Year: 19 97

Plugging proposal received from Dave Dreiling

(company name) C & R Drilling Co. (phone) 303-741-0621

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2074' GL  
Anhydrite 1330'

1st plug at 1330' with 50 sx cement, 2nd plug at 630' with 40 sx cement,

3rd plug at 275' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Scott Alberg  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None X

Operations Completed: Hour: 12 a.m. Day: 2 Month: 9 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 1330' with 50 sx cement,

2nd plug at 630' with 40 sx cement,

3rd plug at 275' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

If additional description is necessary, use BACK of this form.)

**INVOICED**  
1 (XXX) did not observe this plugging.

DATE 9-11-97

WV. NO. 148261

Signed [Signature]  
(TECHNICIAN)

FOR KCC USE:

EFFECTIVE DATE: 8-18-97DISTRICT # 1SGA? Yes X No

State of Kansas

NOTICE OF INTENTION TO DRILL

165-21,710-0000

FORM C-1 7/91

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

Expected Spud Date August 15, 1997  
month day yearSpot 165'N & 165'E of East  
NE NW Sec 4 Twp 17 S, Rg 19 WestOPERATOR: License # 5815  
Name: C & R Drilling Company  
Address: P.O. Box 98  
City/State/Zip: Littleton, Colorado 80160  
Contact Person: Clarence Dreiling  
Phone: 303-933-6200CONTRACTOR: License # 9431  
Name: Vonfeldt Drilling, Inc.Well Drilled For: Well Class: Type Equipment:  
☒ Oil ☐ Enh Rec ☒ Infield ☒ Mud Rotary  
☐ Gas ☐ Storage ☐ Pool Ext. ☐ Air Rotary  
☐ GWWO ☐ Disposal ☐ Wildcat ☐ Cable  
☐ Seismic; ☐ # of Holes ☐ Other

If GWWO: old well information as follows:

Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_Directional, Deviated or Horizontal wellbore? .... yes ☒ no  
If yes, true vertical depth: \_\_\_\_\_Bottom Hole Location: \_\_\_\_\_  
Exp. 2/13/984785 feet from South North line of Section  
3135 feet from East West line of Section  
IS SECTION ☒ REGULAR ☐ IRREGULAR?(NOTE: Locate well on the Section Plat on Reverse Side)  
County: RushLease Name: Yunker Well #: 1

Field Name: \_\_\_\_\_

Is this a Prorated/Spaced Field? .... yes ☒ noTarget Formation(s): LKC - ARBNearest Lease or unit boundary: 495Ground Surface Elevation: 2079 K.B. feet MSLWater well within one-quarter mile: .... yes ☒ noPublic water supply well within one mile: .... yes ☒ noDepth to bottom of fresh water: 130' 250'Depth to bottom of usable water: 220' 630' PERMIANSurface Pipe by Alternate: .... 1 ☒ 2Length of Surface Pipe Planned to be set: 240'Length of Conductor pipe required: 0Projected Total Depth: 3880'Formation at Total Depth: ARB

Water Source for Drilling Operations:

... well ☒ farm pond .... otherWill Cores Be Taken? .... yes ☒ no

If yes, proposed zone: \_\_\_\_\_

240' Alt. II, Reg.

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Daily INIT. am  
 SPUD DATE 8-27-97  
 LENGTH SURFACE PLANNED 340'  
 RESERVE PIT STATUS- REMOVE FLUID LINED  
 after salt sect. bbls. when done bbls.  
 RATHOLED AHEAD? Y N SIZE HOLE  
 SURFACE PIPE 245' CONDUCTOR  
 ANHYDRITE T- B- 1380 ELEVATION 2079 G.L.  
 TD 3880 FORMATION  
 RAN PIPE @ SX DV TOOL SX ALT II DONE Y N  
 Airbuckle Plug @ 3880 Ft. W/ SX  
 Plug./Counell @ 3880 Ft. W/ SX  
 Anhydrite Base @ 1330 Ft. W/ 50 SX  
 1/2 Base Anyh. @ 630 Ft. W/ 40 SX  
 1/2, 1/2 Plug @ 275 Ft. W/ SX  
 Bottom Surface @ 275 Ft. W/ 50 SX  
 40' Plug @ 40 Ft. W/ 10 SX  
 RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX  
 WATER WELL SX (Irr. Well Fond 8)  
 Hauling 264-6  
 TECHNICIAN SA DATE 8-27-97  
 TYPE OF CEMENT 60/40 6% C  
 STARTING TIME : (AM/PM) DATE  
 COMPLETION TIME 12:00 AM DATE 9-2-97  
 CEMENT COMPANY Allied