

1 030934

4-12-88

1070

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-20,702-0000

C N/2 NE, SEC. 14, T 18 S, R 16 W/E
4620 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7671

Lease Name Hunergardt Well # 1

Operator: Providence Energy Corporation
Name & Address: 2761 East Skelly Drive, Suite 705
Tulsa, OK 74105

County Rush 62.08
Well Total Depth 1910 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 400

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number _____

Address Drawer 1431, Duncan, OK 73536

Company to plug at: Hour: 8 a.m. Day: 12 Month: 4 Year: 1988

Plugging proposal received from Joe Foelgner

(company name) Joe Foelgner (phone) 316-793-7519

were: 4 1/2" at 1909' PBD 1877' Perfs at 1864-70'

1st plug circulate 4 1/2" from 1866-0' with 130 sx cement,

2nd plug squeeze 8 5/8" annulus with 175 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:15 p.m. Day: 12 Month: 4 Year: 1988

ACTUAL PLUGGING REPORT 1st plug circulated 4 1/2" from 1866-0' with 130 sx cement,

2nd plug squeezed 8 5/8" annulus with 175 sx cement.

Maximum pressure 550 psi and shut in 500 psi.

RECEIVED

Remarks: No casing recovery. Used 60/40 Pozmix 2% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

APR 19 1988

4-19-88

Signed Steve Durrant (TECHNICIAN)

DATE 4-26-88

CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 20466 AUG 3 1988

SEP 12 1988

FORM CP-2/3
Rev. 01-84

Well flowing 28 B/per hr.
District supervisor issued
emergency plugging authority
to plug without KCC well
plugging authority. All
paperwork will be filed
as soon as possible.

Steve Durrant

TMB 1076-12

Rec. 9-30
Sent Back to
be noted
C. J. ...