

1050370

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,262 -0000

NE SE SW, SEC. 10, T 17 S, R 19 W/E
N SE Corner of
990 feet from ~~N/S~~ section line
W SE Corner of
2970 feet from ~~N/S~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6875

Lease Name Schwindt Well # 24A-10

Operator: Marmik Oil Company
Name & Address: 910 16th Street, Suite 200
Denver, CO 80202

County Rush

Well Total Depth 4042 131.31 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 379

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Chief Drilling Co., Inc. License Number 5886

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 8:00 pm Day: 26 Month: October Year: 19 84

Plugging proposal received from Harold Dinkle

(company name) Chief (phone) 316-262-3791

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1380' with 50 sx cement

2nd plug at 750' with 50 sx cement

3rd plug at 420' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacy (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:45 pm Day: 26 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1380' with 50 sx cement, 2nd plug at 750' with 50 sx cement, 3rd plug at 420' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement.

STATE CORPORATION COMMISSION

OCT 31 1984

10-31-84

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (DATE/dg) observe this plugging.

DATE 11-7-84

Signed Richard W. Lacy (TECHNICIAN)

INV. NO. 4682

10-26