

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21723-00-00
Spot: CSWSWNW Sec/Twnshp/Rge: 15-17S-19W
2970 feet from S Section Line, 330 feet from W Section Line
Lease/Unit Name: WILSON TRUST Well Number: 1
County: RUSH Total Vertical Depth: 3985 feet

Operator License No.: 31514

Conductor Pipe: Size feet:

Op Name: THOROUGHbred ASSOCIATES L.L.C.

Surface Casing: Size 8.625 feet: 260

Address: 8100 E. 22ND ST. - BUILDING 600
WICHITA, KS 67226

Production: Size feet:

Liner: Size feet:

129.51

Well Type: DH

UIC Docket No:

Date/Time to Plug: 12/15/2000 6:30 PM

Plug Co. License No.: 5123

Plug Co. Name: PICKRELL DRILLING COMPANY, INC.

Proposal Rcvd. from: MIKE KERN

Company: PICKRELL DRILLING COMPANY, I Phone: (316) 262-8427

Proposed Plugging Method: 1ST PLUG AT 3920' WITH 40 SX CMT. 2ND PLUG AT 1400' WITH 50 SXCMT. 3RD PLUG AT 700' WITH 80 SX CMT. 4TH PLUG AT 290' WITH 50 SX CMT. 5TH PLUG AT 0-40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: SCOTT ALBERG

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 12/16/2000 1:15 AM

KCC Agent: SCOTT ALBERG

Actual Plugging Report:

1ST PLUG AT 3920' WITH 40 SX CMT. 2ND PLUG AT 1400' WITH 50 SXCMT. 3RD PLUG AT 700' WITH 80 SX CMT. 4TH PLUG AT 290' WITH 50 SX CMT. 5TH PLUG AT 0-40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

RECEIVED
STATE CORPORATION COMMISSION


DEC 19 2000
12-19-00
CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: DP

District: 01

Signed


(TECHNICIAN)

INVOICED

DATE 12/20/00

DEC 18 2000

INV. NO. 2001061158

