

To: 1 120061
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-21-88
API NUMBER 15-165-20,415-0000

NE SW SE, SEC. 13, T 17 S, R 19 W/R
990 feet from S section line

1650 feet from E section line

Lease Name Wilson "O" Well # 2

County Rush 125.48

Well Total Depth 3861 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 572

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Operator: Phillips Petroleum Company
Name & Address: Route 3, Box 20-A
Great Bend, KS 67530

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Phillips Petroleum Company License Number 5229

Address Route 3, Box 20-A, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 21 Month: 1 Year: 19 88

Plugging proposal received from Fred

(company name) Phillips Petroleum Company (phone) 316-793-8424

were: 4 1/2" at 3852' PBDT 3550' Perfs at 3517-21' DV Tool at 1333' with 400 sx cement
1st plug pump in 4 1/2" casing with 600 lbs. hulls and 125 sx cement,
2nd plug pump in annulus between 4 1/2" & 8 5/8" casing with 25 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 21 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped into 4 1/2" casing with 400 lbs. hulls and 100 sx cement.

Pumping pressure 0-1000 psi and shut in 650 psi.

2nd plug pumped in annulus with 1/2 barrel water, 50 lbs. hulls and 5 sx cement.

Pumping pressure 0-300 psi and shut in 300 psi.

Remarks: Used light cement by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did / did not) observe this plugging.

DATE 1-28-88

Signed Duane Rankin (TECHNICIAN)

INV. NO. 19698