

To: 1 120060
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-21-88
API NUMBER 15- 165-20,330-0000

NW SW SE, SEC. 13, T 17 S, R 19 W/E
990 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Wilson "O" Well # 1

Operator: Phillips Petroleum Company
Name & Address: Route 3, Box 20-A
Great Bend, KS 67530

County Rush 125.81
Well Total Depth 3871 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 573

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Phillips Petroleum Company License Number 5229

Address Route 3, Box 20-A, Great Bend, KS 67530

Company to plug at: Hour: 1 p.m. Day: 21 Month: 1 Year: 19 88

Plugging proposal received from Fred

(company name) Phillips Petroleum Company (phone) 316-793-8424

were: 4 1/2" at 3844.5' PBD 3550' Perfs at 3507-13'

1st plug pump in 4 1/2" casing with 600 lbs. hulls and 125 sx cement,

2nd plug pump in annulus between 4 1/2" and 8 5/8" casing with 75 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 21 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped into 4 1/2" casing with 500 lbs. hulls and 100 sx cement. Pumping pressure 0-1000 psi and shut in pressure 400 psi.

2nd plug pumped in annulus between 4 1/2" and 8 5/8" casing with 100 lbs. hulls and 75 sx cement. Pumping pressure 0-200 psi and shut in 50 psi.

Remarks: Used light cement by Allied. No casing recovery.

JAN 27 1988
1-27-88
Wichita, Kansas

INVOICED

(If additional description is necessary, use BACK of this form.)
I (did / ~~did not~~) observe this plugging.

DATE 1-28-88

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 19699