

8-10

1 040306

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,486 - 0000
120' W of
C SW SE, SEC. 35, T 17 S, R 19 W/E

TECHNICIAN'S PLUGGING REPORT

660 feet from S section line
2100 feet from E section line

Operator License # 3701

Lease Name Leo P Well # 1-35

Operator: Balcron Oil Company
Name:
Address P.O. Box 58104
Billings, Montana 58104

County Rush 14/41

Well Total Depth 4351 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1013

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 310 West Central, Suite 117, Wichita, KS 67202

Company to plug at: Hour: 5 a.m. Day: 10 Month: 8 Year: 19 89

Plugging proposal received from Jay Schneider

(company name) Duke Drilling Company (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1260-1306'

1st plug at Arbuckle+50' with 40 sx cement, 2nd plug at 1140' with 50 sx cement,

3rd plug at 600' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:30 a.m. Day: 10 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 3917' with 40 sx cement,

2nd plug at 1045' with 50 sx cemetn,

3rd plug at 600' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 14 1989
8-14-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If applicable) observe this plugging.

DATE 8-17-89

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 25655

8-10

#1 15-165-21,486-0000

FORM MUST BE TYPED
FORM C-1 12/88

State of Kansas
NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date August 1, 1989
month day year

120' W of
C SW SE Sec 35 Twp 17 S, Rg 19 East West

660
2100 feet from South line of Section
feet from East line of Section
(Note: Locate well on Section Plat Below)

OPERATOR: License # 3701
Name: BALCRON OIL COMPANY
Address: P. O. Box 58104
City/State/Zip: Billings, Montana 58104
Contact Person: Alan Townsend
Phone: 406/259-7860

County: Rush
Lease Name: Leo P Well #: 1-35
Field Name: Wildcat

CONTRACTOR: License # 5929
Name: DUKE DRILLING CO., INC. Sig. # 4

Is this a Prorated Field? yes X no
Target Formation(s): Arbuckle
Nearest lease or unit boundary: 660
Ground Surface Elevation: N/A feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 350'
Depth to bottom of usable water: 600'
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 1000'
Length of Conductor pipe required: None
Projected Total Depth: 3850'
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
X well farm pond other

Well Drilled for: Well Class: Type Equipment:
X Oil Inj Infield X Mud Rotary
Gas Storage Pool Ext. Air Rotary
DWAQ Disposal X Wildcat Cable
Seismic; # of Holes

If DWAQ: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth


Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

DWR Permit #:
Will Cores Be Taken? yes X no
If yes, proposed zone:
620' Alt. I Req.

AFFIDAVIT

PUSHER Ray Schneider
TD 4351 FORMATION Arbuckle
SURFACE PIPE 8 3/8" @ 1913
ANHYDRITE 1360 ELEVATION
STARTING TIME & DATE 1306
COMPLETION TIME & DATE 8:30a 8/10
Arbuckle 3813 6040
1st PLUG @ 1045 FT. W/ 570 SX
2nd PLUG @ 600 FT. W/ 570 SX
3rd PLUG @ 40 FT. W/ 10 SX
4th PLUG @ _____ FT. W/ _____ SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ _____ SX
WATER WELL PLUGGED W/ _____ SX
CEMENT COMPANY Allied
TECHNICIAN Steve Hefner

SPUD
8-3-89
1006-851811
Richard
RECEIVED
STATE CORPORATION COMMISSION
AUG 14 1989
8-14-89
CONSERVATION DIVISION
Wichita, Kansas



AUG 1 1989
Chanute, KS

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
 - File Completion form ACO-1 within 120 days of spud date;
 - File acreage attribution plat according to field proration orders;
 - Notify appropriate district office 48 hours prior to workover or re-entry;
 - File salt plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.