

1 120301

9-1

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-165-20,373-A-00-01

SW SW NW, SEC. 22, T 18 S, R 16 W/4

2970 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3456

Lease Name Tammens Well # 1

Operator: AFG Energy, Inc.

County Rush 113.10

Name & Address P.O. Box 605

Well Total Depth 3480 feet

Russell, KS 67665

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 979

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor AFG Energy, Inc. License Number 3456

Address P.O. Box 605, Russell, KS 67665

Company to plug at: Hour: 10 a.m. Day: 1 Month: 9 Year: 19 89

Plugging proposal received from Terry Piesker

(company name) AFG Energy, Inc. (phone) 913-483-6213

were: 4 1/2" at 3470' PBD 3420' Perfs at 1833-3230' (6 sets) DV tool @ 2415' w/200 sx cement

1st plug pump 3 sx hulls and 300 sx cement down 4 1/2" casing,

2nd plug pump 150 sx cement down 8 5/8" between 4 1/2" & 8 5/8" casing.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP - 7 1989  
9-7-89  
CONSERVATION DIVISION  
WICHITA, KANSAS  
STEVE HARRIS  
(TECHNICIAN)

Plugging Proposal Received by \_\_\_\_\_

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 1 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped in 4 1/2" casing with 200 lbs. hulls and 115 sx

cement with hulls mixed in followed with 75 sx cement. Pumping pressure 0-1000 psi

and shut in 800 psi.

2nd plug pumped in 8 5/8" X 4 1/2" annulus with 1/2 bbl. water, pressured to 2000#, cement

to surface in annulus.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

(If applicable) observe this plugging.

INVOICED

DATE 9-13-89

Signed Steve Harris  
(TECHNICIAN)

INV. NO. 25882