

1 070201

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-21,169-00-00
SW NE NE, SEC. 23, T 17 S, R 18 W/E
4290 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name Schwindt Farms Well # 2

Operator: Frontier Oil Company
Name &
Address 1720 KSB&T Building
Wichita, KS 67202

County Rush 120.25

Well Total Depth 3700 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1198

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 am Day: 31 Month: July Year: 1986

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) (316) 938-2457

were: 4 1/2" at 2492' PBD at 2050' Perfs at 2016-22', 2066-71', 2234-44'

1st plug sand back to 1950' and dump 4 sx cement on top of sand through a bailer

2nd plug squeeze well with 2 sx hulls and 100 sx ATL.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:30 am Day: 31 Month: July Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 1950' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 100 lbs. hulls, 100 lbs. hulls mixed with first part of cement, and 150 sx ATL cement.

08-07-1986

Maximum pressure 1000 psi and shut-in 700 psi. AUG 7, 1986

Remarks: Recoved 1700' of 4 1/2" casing. Used ATL cement pumped by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
AUG - 7 1986

observe this plugging.

Signed Dan Goodrow
(TECHNICIAN)

DATE _____

INV. NO. 14661