

15-077-30077-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

04-18-1966
APR 18 1966

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Martin & Keller

Complete Address: 1035 Kennedy Bldg., Tulsa, Oklahoma

Lease Name Squire Well No. # 1

Location NE SE NW Sec. 18 Twp. 31 Rge. 5 (E) (W) W

County Harper Total Depth 3771'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Inc. Box 486 - GREAT BEND, KS.

Address: 815 Wichita Plaza, Wichita, Kansas License No.

Operation Completed: Hour 1:30PM Day 16th Month April Year 1966

The Above well was plugged as follows:

200' of 8 5/8" surface pipe, cement circulated. Hole was filled with
drilling mud to 190', 1st cementing plug, bridged solid with dry cement
and 1/2 sack of hulls on fluid at 190', and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged solid
with dry cement and 1/2 sack of hulls on fluid at 40', and cemented with
10 sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/18/66
INV. NO. 3067-4