

15-077-00276-00-00

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 26 1964  
10-26-1964  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Building, Wichita, KANSAS

Lease Name Poe Well No. #1

Location C-NW-SW Sec. 18 Twp. 31S Rge. 5 (E) (W) X

County Harper Total Depth 4350

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Company Tools

Address:      License No.     

Operation Completed: Hour 9PM Day 19 Month 10 Year 64

The Above well was plugged as follows:

212 feet of 8 5/8 inch surface pipe circulated with 160 sacks cement; hole  
filled with heavy drill mud to 130 feet; 1st cementing plug 1/4 sack hulls  
cemented with 25 sacks. Hole filled to 40 feet with heavy drill mud; 2nd  
cementing plug, 1/4 sack hulls cemented with 10 sacks to base of cellar.  
Rat hole bridged with 2 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Herman Justus  
Well Plugging Supervisor

DATE 10/26/64

INV. NO. 38-11