

15-077-20025-00-00

Form CP-3  
Rev. 6-26-62

**KANSAS**  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

JUN 7 1967

06-07-1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Intent to Drill,  
filed May 23, 1967.

Operator's Full Name Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas 67202

Lease Name Hiebert Well No. # 1

Location C NE NE Sec. 22 Twp. 31 SRge. 5 (E) (W) W

County Harper Total Depth 4665'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Mack Oil Company

Address: 812 Union Center Bldg., Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 10:30AM Day 2nd Month June Year 1967

The Above well was plugged as follows:

224' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole was  
filled with drilling mud to 200', 1st cementing plug bridged with 1/2 sack  
of Gel-Mud and 1/2 sack of hulls on fluid at 200', and cemented with 30  
sacks. Hole was filled with drilling mud to 60', 2nd cementing plug,  
bridged with 1/2 sack of Gel-Mud and 1/2 sack of hulls on fluid at 60', and  
cemented with 25 sacks to the base of the cellar. Rat and mouse holes  
bridged and cemented with 5 sacks.

This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Archie Elving  
Well Plugging Supervisor

DATE 6/7/67  
INV. NO. 5350-W