

15-165-20370-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

FEB 1 1971
CONSERVATION DIVISION
Wichita, Kansas

02-01-1971

Operator's Full Name Glen Rupe

Complete Address 222 Brown Bldg., Wichita, Kansas

Lease Name Temple Well No. 1

Location SE SE NE Sec. 24 Twp. 17 Rge. (E) (W) 20

County Rush Total Depth 1110'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Leben Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 4:45A Day 29 Month 1 Year 1970

The above well was plugged as follows:

RTD 1110' 8 5/8 csg set at 309' cwc Cmt. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 2-1-71

INV. NO. 3290-W