

15-077-00280-00-02

Form CP-3
Rev. 6-26-62

⁴⁰ KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 8 1964
09-08-1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Tenneco Oil Company

Complete Address: 2000 Classen Bldg., Oklahoma City, Oklahoma

Lease Name H. G. Squire Well No. # 1

Location C SW NE Sec. 18 Twp. 31 Rge. 5 (E) (W) W

County Harper Total Depth 4695

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 1:00PM Day 5th Month Sept. Year 1964

The Above well was plugged as follows:

252' of 8 5/8" surface pipe, cement circulated with 150 sacks. 3819'
of 5 1/2" long string, cemented with 100 sacks. Plug back to 3785'. Top
perferation 3650'. Plug was pushed to 3600', and cemented with 5 sacks.
Hole was bailed down to 260', bridge plug was set on fluid at 260',
and 10' of rock bridge, cemented with 25 sacks. Hole was filled with
mud to 40', and 10' of rock bridge, cemented with 10 sacks to the
base of the cellar.

3204' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 9/8/64
INV. NO. 9982-W

15-077-00280-00-00

Mr. Greider:

This is the Tenneco well that
you called Oklahoma City on.

They had neglected to apply
for a Well Plugging Authority.

Archie Elving

RECEIVED
STATE CORPORATION COMMISSION

SEP 8 1964

CONSERVATION DIVISION
Wichita, Kansas