

15-165-20381-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Leben Oil Corporation

Complete Address Box 486 Great Bend, Kansas 67530

Lease Name Ater Well No. 1

Location NW NW SW Sec. 16 Twp. 18 Rge. (E) (W) 16

County Rush Total Depth 3479'

Abandoned Oil Well XK Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pullers

Address Box 221 Great Bend, Kansas 67530 License No. 637

Operation Completed: Hour 11 A Day 23 Month 8 Year 1971

The above well was plugged as follows:

Total Depth 3479' 8 5/8 csg set at 992' cwc 475 sk.

5 1/2 csg set at 3478' cw 125 sk cmt.

5 1/2 csg PBTB 3447' with top perf. (3280')

Set 5 1/2 wood plug at 3250' -poured 10' sd -dumped 5 sk cmt W/dump bailor. (3200-3250)

Cutoff and recovered 2500' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gal & water W/300 lbs hulls, release plug
and pumped 120 sk 60-40 poz W/2% gal. PP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Mansing
Well Plugging Supervisor

DATE 8-31-71
INV. NO. 4245-W