

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 7-11

LOCATION SW/4

SEC. 15 TWP. 18 RGE. 16-W

Dry Hole _____ Abandoned Oil Well _____ Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 1 Lease J. B. Mohr 10/1 #3

Operator The Ohio Oil Company Address Box #710 - McPherson - Kansas

Field _____ County Beck

Total Depth 3674 Feet.

(Describe briefly the manner in which the well was plugged)

Plugged in 25 sacks of cement & 50 sacks mud on
bottom of hole to kill gas - Pulled 7" casing - Plugged in
500 sacks of mud between 15" & 12" casing - Then 500 sacks
Cement between 15" & 12" & shut off water there -
Then pulled 450 ft of 8" casing - & Plugged in 400 sacks
of cement in the 12" casing - Filling hole up to the
surface with Cement - Halliburton Oil Well Cementing
Co. on the job

C. M. Stough
District Conservation Agent

Date 3-22-48

4-1-48

PLUGGING
FILE SEC 15 TWP 18 RGE 16W
BOOK PAGE 7 LINE 11