

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Donald C. Slawson

Complete Address: 408 One Twenty Bldg., Wichita. Kansas

Lease Name Curtis "A" Well No. 1

Location NW NW NW Sec. 9 Twp. 17 Rge. 19 (E) (W) X

County Rush Total Depth 3915'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Co. Tools

Address: _____ License No. _____

Operation Completed: Hour 9:30 Day 21 Month 6 Year 1968

The Above well was plugged as follows:

RTD 3915' 8 5/8 csg set at 262' cwc. Cem. Mat. 100 sc 50-50 poz cem. W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug., 1/2 sc hulls and 10 sc cemento base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Mansur
Well Plugging Supervisor

DATE 6/25/68
INV. NO. 1285-11