



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 28-37

LOCATION NE

SEC. 14 TWP. 18 RGE. 16-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 1 Lease J.D. Mauler

Operator Mr. Louis Mahan Address Box #682 - Tulsa - Okla.

Field Otis County Push

Total Depth 3526 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 15 1/2 - 418 ft. Cemented with 95 sacks of Cement  
13 3/8 - 984 ft. - 7" casing set at 3493 & cemented. Plugged back  
from bottom to 3490 ft. - Pumped 15 sacks of cement on Rock  
Bridge at 3490 ft. Pumped in 100 sacks of Aragal Mud.  
Pulled 290 ft of 7" casing - Pumped 13 3/8 Plug down to  
495 ft - 1st hole in the 13 3/8 casing - then Pumped in 500 sacks  
of cement - Filling hole with cement from 495 ft up  
& to the surface.

Bill Morgan - Pipe Pulling  
Contractor

C. M. Stouck  
District Conservation Agent  
Date 6-30 JUL 2 - 1948  
7-2-48

**PLUGGING**  
FILE SEC 14 18 RGE W  
BOOK PAGE 21 LINE 37

