

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 80-28

LOCATION C SE 1/4

SEC. 14 TWP. 18 RGE. 16-w

Dry Hole \_\_\_\_\_ Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 1 Lease Citel-"B"

Operator Kenwood Oil Co Address 735 Kennedy Bldg. Tulsa Okla

Field \_\_\_\_\_ County Bush

Total Depth 3520 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 15 1/2 - 157 ft. Circulated with cement.  
12 1/2 casing at 955 ft. Circulated with cement.  
7" casing set at 3451 ft. Filled hole with cement from  
bottom up to 3400 ft. Shot off & pulled the 7" casing. Filled with  
mud from 3400 ft to 975 ft. Cement Plug from 975 ft to 950 ft  
Filled with mud from 950 ft to 200 ft. From 200 ft up to the  
surface with cement.  
Ray Ash - Plugging Contractor

RECEIVED  
MAY 31 1949  
5-31-49

C. M. Storch  
District Conservation Agent

Date 5-20-49

**PLUGGING**  
FILE SEC 14-18  
BOOK PAGE 80-28