

KANSAS

Form CP-3
Rev. 6-4-68STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTJ. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202API Number 15-165-38406-00-0 (of this well)

Operator's Full Name PHILLIPS PETROLEUM COMPANY
Complete Address BOX 287 - GREAT BEND, KANS. 67530
Lease Name DEWALD Well No. "B" #2
Location NW-NW-NW. Sec. 13 Twp. 17 Rge. 19 (E) (W) W
County RUSH Total Depth 3843 FE
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated

Plugging Contractor TRIANGLE WELL SERVICE
Address BOX 61 ELLIS, KS. 67637 License No.
Operation Completed: Hour 3:45 PM Day 27 th Month JUNE Year 1980

The above well was plugged as follows:

8 5/8" 278 FE SP. CUC. - 5 1/2" SET AT 3840 FE w/ cmt.
PLUG. BACK. 3538 FE - PERFS 3494 FE - 3498 FE
SQUEEZED AT. 600 FE w/ 300 FE cmt - NO PIPE RECOVERY
ORDERED 180 ST 50 POZ MIX 6% GEL - 15 ST GEL - 2 ST HULL'S.
SPOTTED WITH 2" TUBING.
1 ST PLUG. @ 3490 FE w/ 10 ST GEL AND 35 ST cmt.
2 ND PLUG @ 1448 FE w/ 5 ST GEL - 2 ST HULL'S. AND 60 ST cmt.
3 RD PLUG. @ 283 FE w/ 35 ST cmt. - AND w/ 40 ST cmt IN ANNULUS.
(MAX. PRESSURE - 500 PSI)

I hereby certify that the above well was plugged as herein stated.

(CEMENTED 13 1/2" SAN CMT.)

INVOICED

DATE 7-3-80INV. NO. 2490-WSigned: Marian Schmidt
Well Plugging Supervisor