

15-165-30406-0000

Form CP-3  
Rev. 6-26-62

14

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 5 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Shields Oil Producers

Complete Address: Shields Bldg., Russell, Kansas 67665

Lease Name DeWald Well No. 1

Location NW NW NW Sec. 13 Twp. 17 Rge. (E) (W) 19

County Rush Total Depth 3843

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor:        Co. Tools        By HOWCO

Address:        License No.       

Operation Completed: Hour 3P Day 2 Month 6 Year 1969

The Above well was plugged as follows:

Total Depth 3843' 8 5/8 csg set at 278' cwc 200 sk.

5 1/2 csg set at 3839 1/2 cw 75 sk cmt.

5 1/2 csg squeezed (667 to surface) W/200 sk cmt. (Oct. 10, 1962)

Pumped thru 5 1/2 plug container with 25 sk cmt., 35 sk gel W/3 sk hulls, plug and 50 sk cmt. Max. pres. 1300 lbs. SI pres. 900 lbs.

Cmt. (0-400) Gel & hulls (400-3400) Cmt. (3400-3843 TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey  
Well Plugging Supervisor

DATE 6/5/69  
INV. NO. 9900-W