

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
JUL 12 1976
7-12-76
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -165-20558-0000 (of this well)

Operator's Full Name Phillips Petroleum Company

Complete Address Box 287, Great Bend, Kansas 67530

Lease Name DeWald "B" Well No. 4

Location C SE SW NW Sec. 13 Twp. 17 Rge. (E) (W) 19

County Rush Total Depth 3910'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 12 M Day 10 Month 7 Year 1976

The above well was plugged as follows:

Total Depth 3910', 8 5/8 csg set 616' cwc 380 sk.

5 1/2 csg set 3908' cw 201 sk.

5 1/2 csg PFTD 3685' with top perf. (3535')

Filled 5 1/2 csg W/sd (3685'-3530') dumped 5 sk cem W/dump bailer. (3530'-3500')

Cutoff & recovered 2584' of 5 1/2 csg.

Sun Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water -100 lbs

hulls, 8 5/8" wood plug & 50 sk Comm Cem, -displaced with 8 sk gel & water &

capped with 20 sk Comm Cem.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 7-14-76

INV. NO. 3464-W