

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-1165-20646-0000 (of this well)

Operator's Full Name The Maurice L. Brown Co.

Complete Address 200 Sutton Place Bldg., Wichita, Kansas 67202

Lease Name Payne Well No. 1

Location 30°N 45°E
150'± NW SW NW Sec. 14 Twp. 17 Rge. (E) (W) 19

County Rush Total Depth 3997'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 3:30 P Day 1 Month 11 Year 1978

The above well was plugged as follows:
Total Depth 3997' 8 5/8 csg set 627' cwc 315 sk.
5 1/2 csg set 3995' cw 150 sk cem.
5 1/2 csg PBSD 3960' with top perf. (3915')
Filled 5 1/2 csg W/sd (3960'-3900') dumped 5 sk cem W/dump bailer. (3900'-3865')
Cutoff & recovered 2800' of 5 1/2 csg.
Sun Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/200 lbs
hulls -released cementing plug & followed with 70 sk 50-50 poz 2% -displaced
with 10 sk gel & water & capped with 30 sk 50-50 poz 6% & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED
STATE CORPORATION COMMISSION
11-2-78
NOV - 2 1978

Signed: Leo Massey
Well Plugging Supervisor

DATE 11-3-78
INV. NO. 8472-6
CONSERVATION DIVISION
Wichita, Kansas