



15-165-20115-00-00

ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION  
(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 13 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
02-13-1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Veail of Neven H. Veail has this

date requested permission to plug the following described well:

Mr. Veail guarantees payment of the plugging fee.

Operator's full Name: Neven H. Veail

Complete Address: 1401 McKinley Great Bend, Ks.

Lease Name: Bott Well No. I

Location: C NE SW Sec. 35 Twp. 17 Rge. 20 (E)(W) X

County: Rush Total Depth 4070' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Veail was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace  
70 sc cement thru drill pipe. Heavy mud to 270' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Leo J. Mussey  
Conservation Division Agent