

State of Kansas



15-189-00 685-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
OCT 3 1966
10-3-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Hanna of Anadarko Prod. Co. has this date requested permission to plug the following described well:

Mr. Hanna guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351, Liberal, Kansas

Lease Name: Denman "A" Well No. 1

Location: C SW NE Sec. 1 Twp. 35 Rge. 35 (E) (W)

County Stevens Total Depth 6800' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Hanna was instructed to plug the well as follows:

- 8 5/8" to 1640' circulated w/ cement. T.D. 6800'
- Mud 6800' to 3000' Spot 25 sacks cement 3000' to 2925'
- Mud 2925' to 700' Spot 35 sacks cement 700' to 600'
- Mud 600' to 45' Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Edmund J. Evans
Conservation Division Agent