



15-077-30010-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 - 1965
08-09-1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. T. F. Brown of Gabbert-Jones, Inc. has this

date requested permission to plug the following described well:

Mr. Brown guarantees payment of the plugging fee.

Operator's full Name: Tenneco Oil Company

Complete Address: 2000 Classen Bldg., Oklahoma City, Okla.

Lease Name: Virginia Bush Well No. # 1

Location: C SW NE Sec. 7 Twp. 31 Rge. 5 (E) (W) W

County Harper Total Depth 4600' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brown was instructed to plug the well as follows:

250' of 8 5/8" surface pipe, cement circulated with 175 sacks.

Fill hole with drilling mud to 245', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with hulls, and cement

with 10 sacks to base cellar. Bridge and cement rat hole with

2 sacks.

Very truly yours,

Archie Elving