

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-20285-00-00  
Spot: W2W2SW Sec/Twnshp/Rge: 19-32S-28W  
1338 feet from S Section Line, 4927 feet from E Section Line  
Lease Name: SANDERS RANCH Well #: 3  
County: MEADE Total Vertical Depth: 5730 feet

Operator License No.: 31933  
Op Name: M E KLEIN & ASSOCIATES, INC  
Address: PO BOX 721436  
NORMAN, OK 73070

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4925		WITH 5 SX CMT
PROD	5.5	5730	2830	WITH 225 SX CMT
SURF	8.625	1507		WITH 800 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/04/2013 9:00 AM  
Plug Co. License No.: 33311 Plug Co. Name: PHIL DOLLAR OILFIELD SERVICES, INC.  
Proposal Rcvd. from: MARK KLEIN Company: M E KLEIN & ASSOCIATES Phone: (405) 321-7171

Proposed Plugging Method: CIBP ON BOTTOM. PLUG AT 1520' WITH 15 SX GEL & 50 SX CMT. PLUG AT 750' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/04/2013 11:15 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4925' WITH 5 SX CMT. 1ST PLUG AT 1520' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 750' WITH 40 SX CMT. 3RD PLUG AT 58' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5594	5597		
4970	4976		

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 15 2013

CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED 60/40 POZMIX 4% GEL BY PHIL DOLLAR OILFIELD SERVICES.

Plugged through: TBG

District: 01

Signed Eric Maclaren  
(TECHNICIAN)

RECEIVED

APR - 5 2013

KCC DODGE CITY

BAW