

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-10078-00-00
Spot: NESWNW Sec/Twnshp/Rge: 36-32S-11W
3630 feet from S Section Line, 4290 feet from E Section Line
Lease Name: STONE Well #: 1
County: BARBER Total Vertical Depth: 4523 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4523	2830	WITH 100 SX CMT
SURF	8.625	350		WITH 100 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/29/2013 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: SCOTT HAMPEL Company: MCCOY PETROLEUM Phone: (316) 636-2737

Proposed Plugging Method: PUMP 35 SX CMT & 100# HULLS ON BOTTOM. PLUG AT 640' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 03/29/2013 5:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 35 SX CMT & 250# HULLS ON BOTTOM. 1ST PLUG AT 640' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 44' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4454	4492		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

APR 15 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED

APR - 8 2013

KCC DODGE CITY

Signed

Michael Maier
4/23/13
(TECHNICIAN)

Form CP-2/3

AM